Solar Energy Technologies Program Peer Review



Energy Efficiency & Renewable Energy



Thermochemical Energy Storage for Stirling Concentrating Solar Power Systems CSP Program Team

Robert S Wegeng

Pacific Northwest National Laboratory robert.wegeng@pnl.gov May 25, 2010

This presentation does not contain any proprietary, confidential or otherwise restricted information

Overview

Timeline

- Project Start: Jan 20, 2010
- Project End: Dec 31, 2012
- Percent Complete: 10.6% (as of May 1, 2010)

Budget

- Total Project Funding: ۲
 - DOE Share: \$747,974
 - Contractor Share: \$49,912
- Funding received in FY09: 0
- Funding for FY10: \$747,974 ${\color{black}\bullet}$

Barriers

Capacity factors and Levelized Cost of Electricity (LCOE) for CSP systems

U.S. DEPARTMENT OF

Partners

- **Project Lead: PNNL**
- Interactions/Collaborations: Infinia Corporation

Challenges, Barriers or Problems



- Market Challenges, Barriers or Problems to be Addressed
 - Improving capacity factors for dish-Stirling power generators from <20% to greater than 40% in the near-term, and greater than 90% in the longer-term
 - Reducing the Levelized Cost of Electricity (LCOE) of dish-Stirling power generators to 7¢/kWh
- Relevance: Successful demonstration of Thermochemical Energy Storage (TcES) for dish-Stirling units:
 - Enables power generation during periods when sunlight is unavailable
 - Increases dish-Stirling capacity factors and reductions in LCOE
 - Enables dish-Stirling units to function as intermediate, loadfollowing power generation systems

Relevance

Energy Efficiency & Renewable Energy

U.S. DEPARTMENT OF

- Project Objective
 - Perform preliminary development activities including an on-sun, proof-of-concept demonstration of a high efficiency, solar TcES system based on the integration of compact, process-intensive microchannel reactors and heat exchangers
- Support to DOE Goals
 - This objective supports DOE goals to increase the use of CSP in the USA, making CSP competitive in the intermediate power market by 2015 and in the baseload power market by 2020

Approach

Energy Efficiency & ENERGY **Renewable Energy**

U.S. DEPARTMENT OF

- Evaluate multiple TcES chemistries and cycles
- Examples include:
 - Ammonia Decomposition and Resynthesis
 - $2NH_3 \leftrightarrow N_2 + 3H_2$
 - Hydrocarbon Conversion
 - $CH_4 + H_2O \leftrightarrow OO + 3H_2$



Approach

ENERGY Energy Efficiency & Renewable Energy

 Provide TcES conversions using highly efficient, microchannel reactors and heat exchangers





ENERGY Energy Efficiency & Renewable Energy

 Initial Concept: Integrated TcES with dish-Stirling power generator





Approach

ENERGY Energy Efficiency & Renewable Energy

• Project Timeline



Collaborations

ENERGY Energy Efficiency & Renewable Energy

- PNNL Lead Role
- Infinia Corporation Subcontractor to PNNL
- Tasks
 - Task 1 System Analysis and Tradeoff Study PNNL Lead
 - Task 2 Test System Development Infinia Lead
 - Task 3 Design and Fabrication of Chemical Reactor Components – PNNL Lead
 - Task 4 Demonstration of Solar TcES Operations PNNL and Infinia

Accomplishments / Progress / Results

ENERGY Energy Efficiency & Renewable Energy

- System Analysis and Tradeoff Study Completed (ahead of schedule)
 - Various chemistries/cycles evaluated
 - Hydrocarbon conversion cycle selected for demonstration
 - Go / No-Go Review completed
- Reactor Design Work Underway (ahead of schedule)
- Proof-of-Concept Demonstrations to be performed in 2011 at Infinia

Budget Status and Potential for Expansion

ENERGY | Energy Efficiency & Renewable Energy

- Project Start: January 20, 2010
- DOE Share (\$747,974):
 - Spending to Date on DOE Share (as of End of April):
 - \$79.4K (10.6% of total): Variance of -\$5.8K (-6.83% of planned)
- Infinia Cost Share (\$49,912)
 - Infinia subcontract being established
- If additional funding were provided:
 - Accelerate project: Complete on- and off-sun TcES demonstrations in CY 2010
 - Accelerate hardware development perform extensive/intensive reactor testing and development
 - Establish beta-testing program

Energy Efficiency & Renewable Energy

U.S. DEPARTMENT OF

- FY2011: On- and off-sun proof of principle testing for one TcES cycle
 - May 2011
- Additional reactor testing and development if additional funds are provided

Summary Slide

- Microchannel reactors and heat exchangers enable efficient Thermochemical Energy Storage (TcES) for CSP power generation systems
- TcES based on hydrocarbon cycles (closed- and open-cycles) provide reasonable efficiencies
- TcES based on hydrocarbon cycles (closed- and open-cycles) can improve capacity factors and LCOE
 - Eliminates need for alternative, standby fossil fuel facilities for periods when sunlight is unavailable
 - Enables transition to intermediate/loading following applications by 2015
 - Enabling transition to baseload power generation by 2020
 - Provide a possible route to the production of solar-based transportation fuels (not part of this project)
- Initial on-sun demonstration planned in 2011
- Path to commercialization is clear