



Tower Receiver Development

Concentrating Solar Power Program Team

Kris Miner

Pratt & Whitney Rocketdyne

Kristan.Miner@pwr.utc.com, (818) 586-7854

May 26th, 2010

Timeline

- Project start: Oct. 2008
- Project end: Sept. 2011
- Percent complete: 30%

Budget

- Total project: \$2.88M
 - DOE share: \$1.86M
 - Contractor share: \$1.02M
- FY09: \$389K
- FY10: \$817K

Barriers

- Barriers addressed
 - Performance
 - Reliability
 - O&M cost

Partners

- Project lead: Pratt & Whitney
Rocketdyne
- Interactions: Sandia Test Facility
& sub-tier vendors

- Technical risk was demonstrated with Solar II
 - Main barrier is overall CSP plant capital cost
- Capital cost is being addressed
 - Selecting more cost effective materials
 - Removing design complexity
 - Reduce amount of parts
- Importance of reducing the capital cost is very high
 - Make CSP competitive with traditional energy plants
 - Capital cost dominates LCOE
 - Requires less external financing
 - Increases likelihood that CSP plants will be built



Tubes



Manufacturing



Installation

This presentation does not contain any proprietary, confidential, or otherwise restricted information.


- Performance important to the economic viability of CSP
 - Higher performance
 - Higher energy efficiency
 - Lower LCOE
- Performance barrier addressed in Phase II design
 - Receiver designed for optimum thermal characteristics
 - Materials & coatings selected based on optimum optical characteristics
 - High absorptivity/low emissivity for sunlit regions
 - Low absorptivity/high emissivity for heat shield regions



Performance barrier

Tube materials

Tube coatings



This presentation does not contain any proprietary, confidential, or otherwise restricted information.

- Reliability and O&M costs are related
 - Addressed in the design phase
 - Designing in durability to lower frequency of O&M
- Reliability / O&M barriers evaluated during testing
 - Will be implementing and practicing on-site
 - Tube crack repairs
 - Tube replacements
 - Will be monitoring the O&M issues concerned with:
 - New header and tube designs
 - Tube coatings
 - Heat shield design & materials



Reliability/O&M cost
barrier

Tube durability

Re-application of
coatings

Tube
repairs/replacements




This presentation does not contain any proprietary, confidential, or otherwise restricted information.

- Solving O&M cost issues critical to the future success of CSP
 - Understanding issues will limit plant downtime
 - Known fixes for problems will speed repair time
 - Goal is to perform O&M in a set timeframe throughout the year




This presentation does not contain any proprietary, confidential, or otherwise restricted information.

- Overall project objective:
 - Validate manufacturability of large scale receivers
 - Test receiver in prototypic on-sun conditions
 - Design for lowering the LCOE
- Objectives for the period May 09 – May 10
 - Design for lowering the capital cost and lowering the O&M cost
 - Select materials for improving the reliability and lowering the O&M cost
 - Select tube coatings that improve performance and increase reliability
 - Select heat shield materials that improve reliability and lower the O&M cost



This presentation does not contain any proprietary, confidential, or otherwise restricted information.

- Overall technical approach
 - Review what was achieved in the past (Solar II)
 - Understand current design of large receivers
 - Understand solar operating conditions
 - Innovate design
 - Geometries
 - Materials & processes
 - Finalize design
 - Fabricate hardware
 - Test subscale receiver article
 - Evaluate data
 - Make recommendations for future designs
- Design/Build/Test addresses technical barriers by:
 - Providing opportunity to optimize the cost
 - Implementing higher performance characteristics
 - Learning from the process of build & test
 - Discover valuable information on reliability & O&M



Facility to
be new
from this
level up




Receiver installed at
Sandia

- Receiver project not integrated with other Solar Program research
 - Would integrate with the Baseload Concentrating Solar Power FOA
 - Assuming project was approved
 - Receiver could be utilized again
- FY10 – Milestones & Go/No go decision
 - Milestone #1: Hold Critical Design Review on June 29, 2010
 - Milestone #2: Submit Phase II Report by August 31, 2010
 - Go/no go decision is scheduled for Sept 2010
 - Currently on schedule
 - Complete design
 - Design review
 - Phase II report
- FY11 - Milestones
 - Finish fabrication of receiver by March 31, 2011
 - Complete testing by Sept. 30, 2011
 - Finish project report and production scenarios by Oct. 31, 2011


- Previous accomplishments in FY 09
 - Completed Preliminary Design Review and Phase I report
 - Received authorization to proceed to Phase II
 - Created a preliminary design that addressed the three barriers
 - Capital cost, performance, and reliability/O&M cost
- May 09 – May 10
 - Finalized overall design of the receiver
 - Designed to address all the barriers
 - Finalized two tube materials
 - Achieves objective on lowering capital cost and improving reliability
 - Finalized repair processes to be demonstrated during testing
 - Remove & replace a tube and In-place tube repairs
 - Finalizing four tube coatings
 - Objectives: lower capital cost, increase reliability & lower O&M

Note: No data to present at this time. Data from testing will be gathered during Phase III.


This presentation does not contain any proprietary, confidential, or otherwise restricted information.



Receiver Showing Internal Details



Receiver Insulation




Assembled Receiver

- FY10 Project Plans
 - Finalize design
 - Perform Critical Design Review
 - Release all drawings
 - Procure long lead hardware
 - Submit Phase 2 report
 - Proceed thru Go/No Go gate with a “Go” decision
- FY11 Project Plans
 - Procure remaining hardware
 - Fabricate & test receiver panel at Sandia
 - Issue final report including test results & production scenarios

This presentation does not contain any proprietary, confidential, or otherwise restricted information.

- Project path well defined
- Risks mitigation in place
 - Drawing risk managed by:
 - Correct level of personnel
 - Tools needed to complete the task
 - Fabrication risk is managed by:
 - Selecting proficient vendors
 - Maintaining good communication
 - Involved in fabrication process
 - Testing risk is managed by:
 - Good upfront communication
 - Coordination with Sandia
 - Clear & concise test plan
 - On site personnel during testing



This presentation does not contain any proprietary, confidential, or otherwise restricted information.

- No collaborators for this project
- Project interactions with Sandia (NSTTF)
 - Test facility for this project
 - Federal laboratory
 - Within the DOE Solar Program
 - Extensive interaction
 - Plan & coordinate testing
 - Integration of the hardware in the facility
- Project interactions with sub-tier vendors
 - Hardware procurement & fabrication
 - Independent companies
 - Outside the DOE Solar Program
 - Extensive interaction
 - Communicate design requirements
 - Answer questions



- On schedule
 - Finish design
 - Hold Critical Design Review
 - Submit Phase II report, end of August 2010
- Very encouraged with the design
 - Addressing three technical barriers
 - Capital cost
 - Performance
 - Reliability & O&M cost
- Fabrication and testing in 2011
 - Data will assist design of future CSP plants

