

Energy Efficient Design in a Design-Build Project

Kevin Brettmann

Director, Science & Technology, JE Dunn Construction, @jedunn

Adam Denmark, AIA, LEED AP BD+C

Principal, SmithGroupJJR, @Adam_SGJJR

#NRELESIF



National Renewable Energy Laboratory (NREL)
Energy Systems Integration Facility
Golden, Colorado

Vicon Business Media

Provider Number: L390

NREL Energy Systems Integration Facility: Design-Build Delivered Energy Performance

Course Number: LDC2013-T06

Kevin Brettmann, Dir. of Science & Technology, JE Dunn Construction

Adam Denmark, AIA, LEED AP BD+C, Principal, SmithGroupJJR

Tuesday, April 9, 2013, 11:20 AM



Credit(s) earned on completion of this course will be reported to **AIA CES** for AIA members. Certificates of Completion for both AIA members and non-AIA members are available upon request.

CES for continuing professional education. As such, it does not include content that may be deemed or construed to be an approval or endorsement by the AIA of any material of construction or any method or manner of handling, using, distributing, or dealing in any material or product.

Questions related to specific materials, methods, and services will be addressed at the conclusion of this presentation.

This course is registered with **AIA**



Course Description

Presenters will discuss how complex energy goals are being achieved for the Energy Systems Integration Facility (ESIF) at the U.S. DOE's National Renewable Energy Laboratory (NREL) using a design/build project delivery method.

The new ESIF will house advanced high bay labs, outdoor test facilities, a high performance computing data center, and one of the most energy efficient office buildings in the world.

Learning Objectives

At the end of the this course, participants will be able to:

1. Understand how an integrated project team drives the delivery of aggressive energy goals.
2. Understand performance based Design Build procurement and delivery process.
3. Learn about the design strategies to achieve aggressive energy goals.
4. Understand the types of laboratory environments required for different energy research areas



ESIF Overview

At a Glance

Integrated research including:

- Building and facility systems,
- Community power generation and microgrids,
- Utility generation, and
- Grids that incorporate renewable energy (solar, wind, hydrogen, advanced vehicles), energy efficiency technologies, electrical systems architecture, and grid interoperability

Labs and Equipment

- 14 fully equipped laboratories
- REDB and Grid simulator
- Centralized SCADA Control Room
- Several outdoor test beds

HPC Data Center


- 10,000 sf Data Center floorplate
- Petaflop scale supercomputer
- Insight Visualization Center



ESIF Snapshot

- Cost: \$135M
- Square feet: 182,500
- Occupants: 200
- Super computer: Petaflop-scale
- State-of-the-art electric systems simulation and visualization in an HPC environment
- Component and systems testing and validation at MW-scale powers
- Integration of functioning systems with utility system simulations for real-time, real-power evaluation of high penetration scenarios
- Construction complete: Spring 2013


Hybrid Process



The Bible



Hybrid Process



What We're Bringing to the Table

Priority Checklist

REQUIRED - Request for Proposal Submission	Provided in the RFP Y/N	Rank
Design and build the facility by integrating safety including operational safety, fire protection and life safety into every phase of the project including design, construction and anticipated use.	Y	1
Accommodate all laboratories, a 200 person office and the High Performance Computing Center (HPCDC) described in the program.	Y	2
Achieve an annualized Power Use Effectiveness (PUE) of 1.06 or lower and an annualized Energy Use Effectiveness of 0.9 or lower for the HPCDC.	Y	3
Key Subcontractors, Personnel and Projects for the Mechanical Electrical Plumbing (MEP) Team and the High Performance Computing Data Center (HPCDC) Team.	Y	4
Provide a schedule with guaranteed Substantial Completion date of October 2011.	Y	5
REQUIRED - After Subcontract Award	Y	
Excess waste heat from the data center above that which is used to heat the facility is exported for use by the remainder of the campus.	Y	6
Research equipment identified in the Program will be state-of-the art at the time of occupancy.	Y	7
Utilize state of the art integrated electrical control systems and displays for the distributed energy laboratories, visualization centers and control rooms.	Y	8
GOALS	Y	
Achieve an average annualized EUE of 0.6 or less for the HPCDC.	Y	9
250 staff office space capacity.	Y	10
An additional 2,000 SF laboratory similar to the Smart Grid Laboratory within the allowed budget.	Y	11
An additional 1,500 SF laboratory similar to the Fuel Quality Laboratory within the allowed budget.	Y	12
Maximize laboratory flexibility to support future technologies.	Y	13
Achieve LEED™ Platinum for the entire facility.	N → Y	14
A facility conducive to captivating and informative tours for up to 20 visitors without disrupting ongoing	Y	15
Visual displays of current facility energy efficiency.	Y	16
Most energy efficient data center in the country.	Y	17
Achieve national and global recognition and awards.	Y	18


Guiding Principles

- ✓ Safety
- ✓ Flexibility
- ✓ Sustainability
- ✓ Quality
- ✓ Value
- ✓ Schedule

Preliminary Performance Baseline Design Submission

Requirements:

- Drawings
- Specs
- Substantiation
- Preliminary Energy Model
- Commissioning Plan
- Quality Assurance Plan
- Preliminary Process Hazards Analysis
- Cost Loaded Schedule
- Preliminary Risk Register
- Certified Cost or Pricing Data (7 volumes w/ full detail)
- Firm Fixed Price (\$97,748,707) – Significant Risk for D/B Team!



**** Successful Preliminary Performance Baseline Submitted on December 7, 2010**

Substantiation

Show me the proof!

- 425 items
- Some items redundant with drawings and specs (lighting analysis required separate study with calculations, presentations, etc)
- 3 months to close out NREL comments (multiple iterations)
- Measurement & Verification remaining
- Organization is key!

	Target	DP-3
HPCDC Annual Power Usage Effectiveness (PUE)	1.06	1.04
HPCDC Annual Energy Usage Effectiveness (EUE)	0.9	0.7
ASHRAE 90.1, 2007	30% better	34%
Office Space Annual Average Energy Use Density (kBTU/sf/yr)	26.7	23.0

[illegible]

Award Fee Incentive Program

To Promote Excellent Performance by the Design-Builder

6 Evaluation Periods

** NREL reserves the right to “rollover” any unearned Award Fee to the next evaluation stage.

Preliminary Design	\$500,000
Design Development	\$375,000
Construction Documents	\$375,000
Substantial Completion	\$750,000
Closeout	\$375,000
12 Month Post Occupancy	\$125,000



Current Project Status

6 Design Packages

- ü DP-1: Foundations, Excavation, Utilities, Precast, Structural Steel
- ü DP-2: Core & Shell
- ü DP-3: Lab Fitout, Interior Finishes
- ü DP-4: Furniture & Signage
- ü DP-5: REDB
- ü DP-6: SCADA



It Takes a Village!



NREL – Energy Systems Integration Facility


Overall Performance Targets

- A High Profile Facility of National Importance
- LEED Platinum for the entire Facility
- Integrated & Sustainable High Performance Design
- National Showcase of Sustainable High Performance Design
- Optimized Energy Use & Re-Use within Building & Campus
- The Most Energy Efficient Data Center in North America

REQUIRED – Request for Proposal Submission	Provided in the RFP Y/N	Rank
Design and build the facility by integrating safety including operational safety, fire protection and life safety into every phase of the project including design, construction and anticipated use.		1
Accommodate all laboratories, a 200 person office and the High Performance Computing Center (HPCDC) described in the program.		2
Achieve an annualized Power Use Effectiveness (PUE) of 1.06 or lower and an annualized Energy Use Effectiveness of 0.9 or lower for the HPCDC.		3
Key Subcontractors, Personnel and Projects for the Mechanical Electrical Plumbing (MEP) Team and the High Performance Computing Data Center (HPCDC) Team.		4
Provide a schedule with guaranteed Substantial Completion date of October 2011.		5
REQUIRED – After Subcontract Award		
Excess waste heat from the data center above that which is used to heat the facility is exported for use by the remainder of the campus.		6
Research equipment identified in the Program will be state-of-the art at the time of occupancy.		7
Utilize state of the art integrated electrical control systems and displays for the distributed energy laboratories, visualization centers and control rooms.		8
GOALS		
Achieve an average annualized EUE of 0.6 or less for the HPCDC.		9
250 staff office space capacity.		10
An additional 2,000 SF laboratory similar to the Smart Grid Laboratory within the allowed budget.		11
An additional 1,500 SF laboratory similar to the Fuel Quality Laboratory within the allowed budget.		12
Maximize laboratory flexibility to support future technologies.		13
Achieve LEED™ Platinum for the entire facility.		14
A facility conducive to captivating and informative tours for up to 20 visitors without disrupting ongoing		15
Visual displays of current facility energy efficiency.		16
Most energy efficient data center in the country.		17
Achieve national and global recognition and awards.		18



Campus Integration




Current Development




The Program

3 HIGH BAY LAB

2 DATA CENTER



Orientation, Daylighting + Natural Ventilation




Site Topography



45' = 3 stories

Campus Connectivity



Office



Entry



Courtyard

ENERGY
SYSTEMS
INTEGRATION
FACILITY



Interior View



Office


Energy Target (Site EUI): **26.7 kBTU/sf/yr**

National Average Site EUI: **90 kBTU/sf/yr**
(CBECS)


Energy Efficiency over National Average
(w/server): **74%**

Energy Efficiency over National Average (w/out
server): **87%**



*22.9 kBTU/sf/yr under current model



- The Data Center that serves the ESIF office is located in a separate building and NREL wanted to assign 65 Watts continuous consumption per employee
- **26.7 kBtu's – 16.84 kBtu's (86% for Server and Equipment plug loads) = 9.9kBtu's left over to design to (current design accomplished in 6.6kBtu's)** (pumps, lights, fans, heating, HVAC)
- Natural ventilation has not been modeled




Energy Reduction Strategies




Efficient Planning – Flexible Modifiable Plan

Shallow 60' office depth allows for cross ventilation and deep light penetration



Office

Floors 2 & 3 – Systems Integration



ACTIVE RADIANT, BEAM,
HEATING & COOLING



SHADING, LIGHT SHELF




OPEN OFFICE



UNDER FLOOR AIR

Intelligent Envelop – Tuned for Daylight and Glare Reduction



Open Office





Office Collaboration



Daylighting Analysis

LEED day lighting requirement: 75% of the regularly occupied area receiving 25 foot candles



High-Bay Lab Building (Area A & B)	Regularly Occupied Spaces Area	42596
	Area Achieving EQc8.1 Requirements	30316.4
	% of Area Achieving EQc8.1	71.2%

Data Center Building (Area C)	Regularly Occupied Spaces Area	5901
	Area Achieving EQc8.1 Requirements	5566.4
	% of Area Achieving EQc8.1	94.3%

Office Building (Area D)	Regularly Occupied Spaces Area	29424
	Area Achieving EQc8.1 Requirements	25628.2
	% of Area Achieving EQc8.1	87.1%

Project Totals	Regularly Occupied Spaces Area	77921
	Area Achieving EQc8.1 Requirements	61510.9
	% of Area Achieving EQc8.1	78.9%

Data Center, Conferencing & Insight Center




Section



Data Center

- 2.5 MW – Day one capacity (Utility \$500K/yr/MW)
- 10 MW – Ultimate Capacity
- Initial 400 Teraflop
- No Vapor Compression for Cooling




Data Center

Summer Cooling Mode

PUE – Power Utilization Efficiency
*Total Energy Used by Facility /
Energy used by Computing Equipment*

Typical Data Center = 1.5 – 2.0
NREL ESIF = 1.04

* **30%** more energy efficient than
your typical “green” data center



Data Center


Winter Cooling Mode

EUE – Energy Utilization Efficiency
How efficient are we using the waste heat to heat the rest of the building?

RFP Target = .9 (*use 10% of waste heat*)


NREL ESIF = .7 (*we use 30% of waste heat*)

* We used **20%** more of the waste heat day one. (*more with future campus loops*)



Data Center – Cooling Strategy

- Air Cooling for Legacy Equipment handles **10%** of total Load
- Hydronic Cooling for High Performance Computers handles **90%** of total load



Data Center



Data Center on Display



Conferencing & Insight Center



Conference



Insight Center




Visualization



High Bay Lab




High Bay



High Bay



High Bay Testing Areas



Power Systems Integration Laboratory



Energy Storage Laboratory



Material Characterization Laboratory



Manufacturing Laboratory






REDB

Isolated Testing



Electrical Characterization Laboratory



High Pressure Test

Energy Systems Integration Laboratory





Outdoor Testing

Showcase



Tour Corridor



High Bay Laboratory Strategies

- § Air handling units to provide direct / indirect evaporative cooling and humidification for minimum ventilation
- § High efficiency, variable air volume hoods connected to a central laboratory exhaust system. System varies stack velocity based on wind speed and wind tunnel testing
- § Heat rejection from data center utilized for space heating through the use of active chilled beams/ fan coil / VAV terminal heating coils depending on space type
- § Research chilled water loop configured to reject cooling to HPCDC during testing periods



Questions?

#NRELESIF

Kevin Brettmann
Director, Science & Technology, JE Dunn Construction, @jedunn

Adam Denmark, AIA, LEED AP BD+C
Principal, SmithGroupJJR, @Adam_SGJJR

National Renewable Energy Laboratory (NREL)
Energy Systems Integration Facility
Golden, Colorado

