

# TC Legend Homes, LLC

19th Ave. | Bellingham, WA | TCLegendHomes.com















### PROJECT DATA

- **Layout:** 4 bdrm, 2.5 bath, 2 fl, 2,463 ft<sup>2</sup>
- Climate: IECC 4C, marine
- Completed: May 2016
- Category: custom for buyer

#### **MODELED PERFORMANCE DATA**

- **HERS Index:** without PV 44, with PV -2
- Projected Annual Energy Costs: without PV \$1,053, with PV \$25
- Projected Annual Energy Cost Savings:
  (vs home built to 2012 IECC) without
  PV \$811, with PV \$1,889
- Annual Energy Savings: without PV 9,453 kWh, with PV 20,993 kWh

## CONTACT

Ted Clifton tclegendhomes@gmail.com 360-220-2119

## KEY FEATURES

- Walls: R-29, 6" SIP taped at all interior and exterior joints, fiber cement siding.
- **Roof:** R-42, 10" SIP taped at all interior and exterior joints. Ice-and-water shield, asphalt shingles.
- Attic: None.
- Foundation: R-23 ICF stem walls, R-20 rigid foam under slab.
- Windows: Triple-pane, vinyl-framed, low-e windows, U=0.21.
- Air Sealing: 0.60 ACH 50
- Ventilation: Timered exhaust fans.
- **HVAC:** Evacuated tube solar hot water and 4.5 COP air-to-water heat pump for in-floor radiant hydronic heat.
- Hot Water: Air-to-water heat pump, 4.5 COP.
- Lighting: 100% LED
- Appliances: ENERGY STAR refrigerator, clothes washer, range hood; induction cooktop.
- Solar: 9.5-kW PV, evacuated tube solar hot water.
- Water Conservation: Low-flow fixtures; centrally located water heater.
- Other: Low-VOC paints and finishes. Electric car charging station.





