

C & B Custom Homes

The Antelope Plan | Cottonwood, AZ | CandBHomes.com













PROJECT DATA

• **Layout:** 3 bdrm, 2 bath, 2 fls, 1,663 ft²

• Climate: IECC 4B, mixed-dry

Completed: May 2020

Category: Custom Spec

MODELED PERFORMANCE DATA

- HERS Index: without PV 44; with PV 11
- Annual Energy Costs: without PV \$1,200; with PV \$600
- Annual Energy Cost Savings: (vs typical new homes) without PV \$1,000; with PV \$1,650
- Annual Energy Savings: without PV
 3,000 kWh, 350 Therms; with PV
 9,000 kWh, 350 Therms
- Savings in the First 30 Years: without PV \$48,000; with PV \$75,800

CONTACT

Chris Spannagel 928-634-8453 chrs.candb@gmail.com

KEY FEATURES

- Walls: 2x6, 16" o.c., R-29 total: R-24 spray foam cavity insulation, house wrap, 1" R-5 rigid foam sheathing, type "F" acrylic modified stucco.
- Roof: Truss gable roof, peel-and-stick membrane on all roof, cement tile cladding, ES Cool Roof.
- Attic: Conditioned attic: 7" R-26 open-cell spray-foam on underside of roof deck.
- Foundation: Daylight basement: grouted CMU, 1" R-5 exterior rigid foam. Under slab: 2" R-10 foam at perimeter 48".
- Windows: Double-pane, argon-filled, low-e coatings, vinyl single-hung frames. U=0.29, SHGC=0.23.
- Air Sealing: 2.6 ACH 50. Spray-foam cavity insulation, sill plate gaskets and caulk, all penetrations thru top plates and walls foam sealed.
- Ventilation: ERV, MERV 9 filter.
- HVAC: 96% AFUE gas furnace. AC 16 SEER. Small-diameter high-velocity ducts.
- Hot Water: Tankless gas, 0.96 efficiency, central manifold with PEX piping, recirculation pump.
- Lighting: 100% LED.
- Appliances: ENERGY STAR appliances.
- Solar: 3.55-kW; integrated micro-inverters.
- Water Conservation: EPA WaterSense fixtures, drip irrigation in landscape.
- Energy Management System: Wi-Fi and Bluetooth compatible thermostat.
- Other: Zero-VOC paint and cabinets, UL Greenguard Gold hard flooring.





