

2022 DOE Vehicle Technologies Office Annual Merit Review June 21, 2022

Simultaneous Greenhouse Gas and Criteria Pollutants Emissions
Reduction for Off-Road Powertrains

Project ID: ACE171
DOE Contract # DE-EE0009873

Principle Investigator: Dr. James McCarthy, Jr.
Eaton

June 21, 2022

Overview

Timeline

- Project start date: 2/1/2022
- Project end date: 5/1/2025
- Percent complete: Just Started


Budget

- Total project funding: \$2,978,523
 - DOE share: \$2,377,904
 - Contractor share: \$600,619
- Funding for FY 2022
 - Budget Period 1: \$1,550,378
 - (ending 4/30/2023)

Barriers and Technical Targets


- Building high efficiency, off-road, future engine
 - Adding cylinder deactivation with transient controls and
 - Adding the high efficiency turbocharger with transient exhaust gas recirculation (EGR) pump controls.
- Validated operation in Budget Period 1

Partners




DOE Program: Future Engine & Aftertreatment

Off-Highway Engine of the Future



Modular Advanced Aftertreatment System



Future Testbed (Modular) is a Single Pass Aftertreatment System with a DPF



Baseline: Engine and Aftertreatment

FPT Cursor 13L Engine
407 kW @ 2100 rpm



Aftertreatment System is Flow Optimized for minimal backpressure and no Diesel Particulate Filter

Tailpipe Out



Program Baseline: US Final Tier 4 Engine & Aftertreatment System

- Flow Optimized (minimized backpressure)
- No DPF (minimized backpressure)

Test Cycles and Evaluation Metrics

- Current Regulatory Cycles
 - Non-Road Transient Cycle
 - 8 Mode Cycle



Metric:
NOx:
GHG:

Today:
<0.4 g/kW-hr
Needs to be measured

Program Deliverable:
<0.04 g/kW-hr (>90%)
> 10% Reduction

- Tomorrows Regulatory Cycle
 - New Off-Highway Low Load Cycle

Program Deliverable:
Quantify **NOx** and **GHG** Reduction
(no current standard)
Characterize LLC between off-highway and on-road

- Field (in-use) Application Cycles
 - Cycles To be Determined in Budget Period 1
 - Candidates include:


| Table 1: Multiple Off-Road use-cases, duty cycles and emissions challenges | | |
|--|--------------------------------------|---|
| Application | In Use Cycle | GHG and NOx Challenges |
| Heavy Tillage | High load cycle | Efficiency at max power is critical, while maintaining Exhaust Gas Recirculation (EGR) flow |
| Planting | Mix of loads with smooth transitions | Efficiency at multiple operating point |
| Scraper | High load cycle with transients | Multiple NOx spikes |
| Trailer Grain Cart | Low speed / low load cycle | Low exhaust temperature |
| Air seeder | Low and medium load | Insufficient heat in aftertreatment transients |

Program Deliverable:
Quantify **NOx** and **GHG** Reduction
(no current standard)


All Tests Conducted with Hydrothermal End of Life Aftertreatment Catalysts

Proposed Baseline Testing GHG Adjustment

- Measure NOx and GHG on all cycles
 - US Cursor 13L engine + MY2022 Production Aftertreatment (end of life hydrothermally aged)
- CFD Simulation Configurations
 - Configurations
 - Start with Final Tier 4 Aftertreatment (flow efficient path without a DPF)
 - Part 1: Configure Aftertreatment into Single Path
 - Part 2: Add DPF to Single Path
 - Operating Conditions (re-use same flows as those from final Tier 4)
 - Rated Speed (full load)
 - Max Power
 - Assessment
 - Part 1: Capture incremental backpressure impact for single path in terms of GHG
 - Part 2: Capture incremental backpressure impact for DPF in terms of GHG
 - Add two numbers together (Part 1 + Part 2)
 - Assumption: this delta is applied across all speeds and loads
 - GHG adjustment across cycles
 - Take measured GHG for each cycle baseline cycle (regulatory, new low load and field cycles) and correct with the CFD numbers for (1) single path and (2) added DPF.



GHG Correction for:
Single Path with DPF



GHG Reduction: Future Engine + Modular System Compared to GHG Adjustment for Baseline

This will represent a ~MY2024 Aftertreatment System with a DPF as our baseline

Strategies for Simultaneous NOx and GHG Reduction

Table 1: Key strategies to achieve 10% GHG reduction and 90% NOx reduction

| | Strategies | GHG benefit | NOx benefit |
|---|---|-------------|-------------|
| 1 | Increase compression ratio | 2% | |
| 2 | Increase boosting / eliminate pumping losses | 3% | |
| 3 | Reduce engine parasitic losses | 2% | |
| 4 | Reduce engine displacement at low load | 2% | <40% |
| 5 | Lower N2O formation (in Aftertreatment) | 3.5% | |
| 6 | Lower engine-out NOx while minimizing pumping losses | -1% | 33% |
| 7 | Aggressive exhaust and Aftertreatment thermal management (net) | 0% | 5% |
| 8 | Increase NOx conversion efficiency while minimizing incremental backpressure | -1% | 85% |
| 9 | Functional re-use of technologies to achieve a system incremental cost <\$4,000 | | |

Table 8: NOx and CO2 testbeds reductions relative to State-of-Art and Tier 4b emissions

| Testbeds | NOx reduction | | GHG reduction | |
|-----------------------------------|----------------|----------------|---------------|-----------------|
| | Engine | Aftertreatment | Engine | Aftertreatment |
| Thermodynamics and parasitic loss | None | None | 5%-7% | |
| EGR | 25% to 35% | | -1% to -2% | 3.5% (from N2O) |
| CDA | Up to 40% | Faster warmup | 1% to 4% | |
| Aftertreatment | | 85% | -1% | |
| Heater / eng. controls | | | -1% | |
| Net (cycle dependent) | 90% (tailpipe) | | 6.5% - 12.5% | |

Greenhouse Gas (GHG) quantified in terms of CO₂

Detailed Program Scope

A. OBJECTIVES

Research, develop, & validate aftertreatment system-level strategies capable of $\geq 10\%$ Greenhouse Gas (GHG) reduction and $\geq 90\%$ Nitrogen Oxides (NO_x) reduction for off-road powertrains over multiple duty cycles spanning the diverse applications in the segment, while maintaining affordability and robustness to ensure economic viability.

B. SCOPE OF WORK

The project will be conducted in 3 budget periods:

Budget Period 1: System Design and Testbeds Build: Define meaningful duty-cycles, baseline, and targets to ensure off-road segment coverage. Simulate, design, build, and validate the engine testbed and modular high conversion efficiency aftertreatment testbed.

Budget Period 2: System Exploration and Optimization: Build prototype exhaust thermal management systems and new catalysis modules and incorporate in the modular aftertreatment. Build prototype high conversion efficiency elements and modular testbed allowing mix-and-match components to realize different architectures. Optimize multiple hardware architectures through controls and calibration on the testbeds. Explore and optimize architectures and predict optimum configuration.

Budget Period 3: Limits of Performance Illustration: Build optimum configuration to achieve limits of performance and quantify that performance on testbeds.

Simultaneous NO_x & GHG Reduction

- 90% NO_x Reduction
- 10% GHG Reduction

Build & Baseline: Feb. 1, 2022 to May 1, 2023

- Baseline engine and Aftertreatment (AT) – at ORNL
- Future Engine Commissioned – at ORNL
 - Includes CDA & EGR pump systems
- Modular AT System Built and Aged – Delivered to ORNL

Test: May 1, 2023 to May 1, 2024

- Characterize System Performance Using 5 Configurations
 - LO-SCR + Primary AT
 - Fuel Burner + Primary AT
 - LO-SCR + Fuel Burner + Primary AT
 - E-heater + LO-SCR + Primary AT
 - LO-SCR + DOC-DPF + E-heater + SCR

Final Demo: May 1, 2024 to May 1, 2025


- Construct Final Configuration, Test and Quantify
- Final Report

Progress as of April 2022

Team Assembled, Baseline Configuration Agreed Upon and Project Management Plan Submitted

Program Schedule

| | | | |
|---|---|-------------|-------------|
| ✦ Budget Period 1: System Design and Testbeds Build | | Tue 2/1/22 | Mon 5/1/23 |
| ✦ Task 0.0 – Project Management and Planning: | | Thu 3/31/22 | Thu 3/31/22 |
| Task 0.1 – Kick-Off Meeting: | | Thu 3/31/22 | Thu 3/31/22 |
| ✦ Task 1.1 – State-of-Art System Definition and Performance Metrics | | Tue 2/1/22 | Fri 7/15/22 |
| Subtask 1.1.1 - State-of-Art system definition: Create Cursor 13/Tier IVb baseline. | | Fri 4/22/22 | Fri 6/24/22 |
| Subtask 1.1.2 - Develop duty cycle and GHG and Nox performance targets | | Mon 5/23/22 | Mon 5/30/22 |
| Subtask 1.1.3 - Future engine and Aftertreatment concept and architecture | | Tue 2/1/22 | Fri 6/17/22 |
| Subtask 1.1.4 – Preliminary cost model | | Mon 5/2/22 | Fri 7/15/22 |
| ✦ Task 1.2 – Future Engine Test Development | | Tue 2/1/22 | Tue 4/25/23 |
| Subtask 1.2.1 – Design and fabricate future engine testbed: | | Tue 2/1/22 | Tue 9/27/22 |
| Subtask 1.2.2 – Future engine testbed commissioned at ORNL: | | Fri 8/26/22 | Tue 4/25/23 |
| ✦ Task 1.3 – Modular High Conversion Efficiency Aftertreatment Testbed | | Mon 5/9/22 | Mon 5/1/23 |
| Subtask 1.3.1 – Baseline state-of-art engine + aftertreatment | | Fri 6/24/22 | Thu 8/18/22 |
| Subtask 1.3.2 – Modular aftertreatment testbed commission | | Mon 5/9/22 | Mon 5/1/23 |
| ✦ Budget Period 2: System Exploration and Optimization | | Mon 5/1/23 | Wed 5/1/24 |
| Task 2.1 – System Integration: | | Mon 5/1/23 | Mon 7/24/23 |
| ✦ Task 2.2 – System Exploration and Optimization: | | Mon 5/1/23 | Fri 4/5/24 |
| Subtask 2.2.1 – Test Future Engine with Aftertreatment Configuration 1 | 1 | Mon 5/1/23 | Mon 5/29/23 |
| Subtask 2.2.2 – Test Future Engine with Aftertreatment Configuration 2 | 2 | Wed 11/1/23 | Wed 12/6/23 |
| Subtask 2.2.2 – Test Future Engine with Aftertreatment Configuration 3 | 3 | Fri 12/1/23 | Fri 1/5/24 |
| Subtask 2.2.2 – Test Future Engine with Aftertreatment Configuration 4 | 4 | Thu 2/1/24 | Thu 3/7/24 |
| Subtask 2.2.2 – Test Future Engine with Aftertreatment Configuration 5 | 5 | Fri 3/1/24 | Fri 4/5/24 |
| Task 2.3 – Trade-Off Analysis and Limits of Performance Analysis | | Mon 1/1/24 | Fri 3/22/24 |
| ✦ Budget Period 3: Limits of Performance Illustration | | Wed 5/1/24 | Thu 5/1/25 |
| Task 3.1 – System Integration: | | Wed 5/1/24 | Mon 6/3/24 |
| Task 3.2 – Performance Measurement: | | Mon 6/3/24 | Fri 1/10/25 |
| Final DOE Report | 6 | Mon 1/13/25 | Fri 4/25/25 |



Publication Plan: 6-7 Journal Papers at the end of each major test. Plus, comparison of the LLC between off-highway and on-highway

Summary

- Team is Assembled
- Baseline Configuration Agreed Upon
 - US Final Tier 4 Engine and Aftertreatment
- Greenhouse Gas Correction Agreed Upon
 - CFD to correct baseline → single path aftertreatment with DPF
- Project Management Plan Submitted
- Program Schedule Created
- Publication Plan Established