

by Ideanomics

Wireless Extreme Fast Charging for Electric Vehicles (WXFC – Trucks)

Michael Masquelier | Principal Investigator

Project ID: elt240

June 21st - 23rd , 2022

This presentation does not contain any proprietary, confidential, or otherwise restricted information



WXFC - Trucks Project Overview

Timeline

Project Start Date: August - 2018
Project End Date: July - 2023

Project Complete: 72 %

Budget

Total Project Funding : \$ 9, 838, 240

DOE Share : \$ 4, 292, 137 Contractor Share : \$ 5, 546, 103

Funding for FY 2019 : \$ 1, 249, 762

Funding for FY 2020 : \$ 3, 603, 179 Funding for FY 2021 : \$ 2, 158, 560

Funding for FY 2022: In-progress

Barriers

- Meeting the window of time to deliver a medium voltage feed to the charge site.
- Obtaining necessary permits for the project.
- Acclimating drivers to electric vehicles requires changing driver habits (or other personnel) for plugging in the vehicles and aligning the trucks over the wireless chargers.

Partners

- WAVE, Inc Project Lead
- Cummins, Inc (Cummins)
- Utah State University (USU)
- Schneider Electric (Schneider)
- Total Transportation Services Inc (TTSI)
- Port of Los Angeles (POLA)
- Los Angeles Department of Water & Pump (LADWP)

WXFC - Trucks

Relevance


Impact

- The California Air Resource Board shows that 41% of all greenhouse gas emissions (429.5 MMTCO $_2$ e in California in 2016) is due to transportation.
- 7.8% of all greenhouse gas emissions were from heavy duty trucks.
- Enabler for this major pollution transportation sector to become allelectric.
 - Fully charged vehicles in roughly 20-minutes means minimal down time to refuel and minimal impact on existing route planning.
 - No cables means hands free instant start of charging with no special personnel required.
- Overcoming the charging time obstacle leads to a 3x to 4x reduction in actual fuel costs for vehicle operation.
- Accelerate manufacturing and deployment of electric heavy-duty trucks.


Objectives

- Wireless extreme fast charging
- MV grid to DC converter
- Extreme fast charging capable electric truck

Heavy Duty Truck Production in USA 2011-2021



Zero-Emission Truck Production in USA 2011-2021



WXFC - Trucks Relevance


FOA Objective	WXFC - Truck Expected Outcomes		
Recharge battery in half the time	New system with 500 kW wireless charging		
Develop and verify vehicles equipped with XFC, charger installation demonstration	 W-XFC system deployment and operation at POLA with two Clasee-8 trucks customized to support XFC. Deployment in two stages. First early 500 kW protetype charging and 		
	 Deployment in two stages. First early 500 kW prototype charging and second final deployment at 500 kW. Combined, over two years of evaluation data and best practices. 		
System design and grid infrastructure	 Direct MV 3-phase AC to DC single stage conversion solution to reduce 		
impact	grid integration costs, system size and weight, and improve efficiency.		
Catalyze manufacturing and adoption of electric trucks	Project goal targets key barrier to market adoption.		
	 Over two years of system hardware demonstration and evaluation are performed at one of the world's highest volume shipping ports at a critical time with zero emission requirements in place by 2035. 		

WXFC - Trucks Milestones

Budget Period 1 August 2018 - June 2020	Budget Period 2 July 2020 - July 2022	Budget Period 3 Aug 2022 - July 202	Status
Task 0 : Project Management a			
Task 1 : 500 kW Prototype Development		Tests indicate 5system construfeasibility	
Task 2: W-XFC 500 kW System	Design and Development	 Demonstration 	n of 100 %
Task 3: Fast Charging Electric	Truck Design and Construction	500kW wireles	80%
Task 4: Design and construct MV Grid connected converter			22%
Task 5: 500 kW System Integration and Testing			100%
Task 6: 500 kW System Deploy	20%		

WXFC - Trucks Approach

Design and simulation



Block diagram of the WXFC system from MV grid to truck battery.

WXFC - Trucks Approach

500kW MV Grid Connected AC/DC Supply Approach

- 3-phase unfolder with a soft DC bus two-level output.
- Develop the 3-phase unfolder to achieve direct MV grid connection with switches commutating at the line frequency.
- Design the series stacked isolated DC/DC converters to achieve the voltage step down function from MV naturally with near unity conversion ration to obtain high frequency.

Extreme Fast Charging Capable Electric Truck Approach

- Investigate appropriate battery chemistry (LTO cells or NMC cells)
- Design custom thermal management for the cell to facilitate charging at 3C.
- Select appropriate battery pack capacity and cell chemistry to integrate with electric powertrain applicable to Class 8 drayage applications.

WXFC - Trucks Approach

500kW Wireless Charging System Approach

- Leverage deployment experience with 250 kW charger.
- Use deployment experience to develop 500 kW prototype.
- WAVE has experience integrating with different OEMs.

WAVE WIRELESS BENEFITS

(JAN. 2019 - MARCH 2022)

Range extension miles delivered: 2.126.302

Power delivered: 3,827 MWh

Diesel fuel saved: 545,205 gallons**

Pounds of CO2 saved: 12,954,068**

Pounds of PM2.5 saved: 30,831**



* standard operating range of a BYD K9

** benefits attributed to using wireless charging

WIRELESS-ENABLED FLEET

Total service area: 100 square miles

Wireless charging stations: 12 @ 250kW with three more in 2021

Vehicles: 47 BYD wireless-equipped battery-electric buses

RANGE EXTENSION

Longest route covered: 600 miles (vs. operating range of 155 miles*)

State-of-charge (select routes): Buses end shift with higher SOC than start

Range extension: Double standard operating range in an 8-hour shift*/
Adds over 400 miles during 16 hours of operation

WAREHOUSE & DISTRIBUTION





TRANSIT





Completed the HF transformers fabrication and the initial UL review

External Hardware Coordination

- Coordinated with Schneider Electric to design and receive the AC-DC cabinet
- Coordinated with Schneider Electric to finalize the Motorpact design
- Finalized the initial desk review with UL for the 560-kW design

Internal Hardware Development

- Procured all components needed to construct the 560-kW system
- Constructed all the enclosures needed for the MV Unfolder and all DC-DC modules
- Received and tested all the transformers from the vendor for quality and UL compliance
- Designed and fabricated all circuit boards required for control, communication, sensing, and protections





Unfolder and DC-DC Enclosures



AC-DC Cabinet Received from SE



Fabricated HF Transformers



560kW MV Grid Connected AC/DC Supply Progress


Completed the full 560 kW system simulations and demonstrated the three-port series stacking control

External Software & Control Coordination

- Determined the SE contactor control requirements and incorporated the design into the AC-DC system
- Coordinated with WAVE to evaluate the WPT system dynamics and finalize the control requirements
- Coordinated with WAVE on establishing a communication basis between the USU and the WAVE systems


Internal Software & Control Development


- Demonstrated the three-port series stacking control in hardware.
- Completed the full 560 kW simulations, demonstrating the functionality of the implemented (SE + USU + WAVE) hardware.






2 kW Simulations and Hardware Results







WAVE

by Ideanomics

WXFC - Trucks Technical Accomplishments & Progress

- WAVE Equipment Builds Complete
 - Primary Cabinet (2x)
 - Primary Pads (2x)
 - Secondary Pads (4 2x/truck)
 - Rectifier (2 1x/truck)
- Cummin's Trucks Complete
 - 3C Charging Capable Battery Pack
 - Truck 1 & 2 Construction Complete
 - Truck 1 Delivered to WAVE
- WAVE systems Integration w/ Cummins Truck 1- Complete
 - Secondary Pads
 - Rectifier, Antenna & LV Control Box
- Wireless Charging w/ Vehicle Complete
 - Communications Testing
 - Contactor Operations / Shutdown Function
 - Charging of Individual Pad Sets 250 kW
 - Dual Pad Charging 500 kW
 - 3C Charging of Reconfigured Battery Pack



Cummins Truck @ WAVE



Secondary pads



Charge Testing Set up



Rectifier Unit



- Primary Pads
 - Cost: Same as production 250 kW pad
 - Dimensions:
 - WXFC Primary Pad: ~ 50% smaller



Primary Pads

- Secondary Pads
 - Cost: Same as production 250 kW pad
 - Dimensions:
 - WXFC Secondary Pad : ~ 50% smaller
 - Weight:
 - Total Weight Savings: ~ 500 lbs



Secondary Pads



pads in a lab setting.

2020-21 2021-22

500 kW System	 Production design work completed and on order. 	•	Production charging pads, Primary inverter cabinets, Rectifiers, Cooler and other systems are built and integrated to Truck 1.
Compact Design	 Final design to have 25% weight reduction from original prototype. 	•	Final design is 500 lbs lighter than the current production pad. Both Primary and Secondary pads are 50 % smaller than current production pads.
Validation Testing	 Initial testing was performed between the 	•	Charge testing was done with the production

Max cell temperature reached was 29 °C.

Demonstrated 3C charging with the battery

pads installed to Cummins Truck 1.

pack on the truck.

• Transferred ~ 500 kW between the pads.



Truck requirements

- Class 8-day cab based on TTSI's requirements.
- Battery selected which supports 3C charging, 2C discharging.


Electric Powertrain

• Cummins-developed 330 kW (continuous) central drive

Truck status

- Trucks undergoing validation in Columbus, Indiana (test track and public roads)
- Wireless charging (495 kW) demonstrated at WAVE in Q3 2021

Key vehicle metrics	Target	As designed
Vehicle speed on 6% grade @ 82k lb GCVW	> 30 mph	32 mph
Charge power to 80% SOC (15 minutes)	495 kW	495 kW
Tractor weight	≤ 22.5k lb	22.8k lb
Vehicle range	45 miles	58 miles
Work-day duty cycle	20 hours 160+ miles	20 hours 200+ miles








Site Plan:

- Charger location is now relocated closer to the breaker location.
- Revision of electrical and civil drawings are in progress.
- APP (Application for Port Permits) and Project approval application requests are submitted to POLA. Pending approval.
- Breaker orders submitted to Schneider Electric.





WXFC - Trucks

Response to Previous Year's Reviewers' Comments

Approach

Reviewer: "more details on the feasibility versus the project goals, specifically on a breakdown of anticipated hardware costs versus targets for both charging pad and the vehicle-based hardware."

Response: WAVE was able to accomplish 50 % smaller pad size and around 500 lbs weight reduction with the same cost to a make a current 250 kW pad.

Technical Accomplishments & Progress

Reviewer: "It does appear the team is behind, and it is unclear how much system validation can be accomplished relative to what may have been planned at the beginning of the project"

Response: WAVE and Cummins have completed the integration and charge testing as planned and met the milestone targets of 500 kW power transfer and 3C charging.

Collaboration & Coordination Across Project Team

Reviewer: "The reviewer stated that the integration of the design progress reflects significant collaboration and coordination by the various partners."

Response: Timely communication and quick responses between the teams have helped resolve issues faster and mitigate delays in the project.

Proposed Future Research

Reviewer: "It is not clear where the project team is relative to the 92% efficiency goal."

Response: In the initial charge testing, WAVE has achieved > 92% efficiency from grid to battery with 480 V feed. Plan to complete the final charge testing this summer and present the results.

Relevance

Reviewer: "The ability to minimize "fueling times" is critical to making BEVs of this size feasible to that particular population of vehicles."

Response: The current project addresses this issue; WAVE was able to significantly reduce the charge time by transferring energy at 3C rate.

Resources

Reviewer: "The reviewer stated that the main resource that appears to be strained is the schedule timeline due to unanticipated delays in establishing the MV grid power supply"

Response: Supply chain is still a big concern; WAVE has taken steps predicting further delays to MV equipment and ordered power supplies in advance.

WXFC - Trucks Collaborations & Coordination



Wireless XFC System



MV Grid Connected AC-DC Supply, Research partner

Port Trucks Partner



Electrical Supplier and Industrialization Partner



Deployment partner



Electric Utility



University.

WXFC - Trucks Remaining Challenges & Barriers

MV-Grid Converter:

- MV cabinets delayed due to supply chain issues; MV grid converter validation to be performed at USU separately.
- Replace MV power supply with resonant power supply units.

Site Deployment & Project Demonstration:

- Final project approvals pending from POLA.
- Breaker inspection and procurement of breakers in time before deployment.
- Demonstration at site will be performed with a 480V feed instead of 4160V feed.

WAVE System:

- Automation of charging system to deliver 500 kW power.
- Truck integration and final charge testing with Truck -2.

Truck Design:

• 6-phase inverter validation and thermal management of the battery system.

WXFC - Trucks Proposed Future Research

Future Research Opportunities:

- Battery: To improve long-term commercial viability, industry needs to develop a low-cost, higher energy density 3C charge (continuous) capable battery.
- Grid Feed: Optimize MV-to-DC converter for various electric utility MV voltages available.
- Thermal: Minimization of heat generated and novel thermal materials.
- Operator Cost: Addition of stationary storage to offset demand and TOU charges.
- System : Overall improved system-level efficiency

Any proposed future work is subject to change based on funding levels.

WXFC - Trucks Summary

This project brings together all three critical components needed to solve the barrier for adoption of electric heavy-duty vehicles:

- High-efficiency MV Grid to lower energy costs and reduce total footprint of equipment.
- High-efficiency, high energy density wireless extreme fast charger.
- An all-electric vehicle capable of high c-rate charging and equipped to handle a wireless charging system.

The project's overall system approach is driving research that will result in a highly cost-effective solution that will make adoption of all-electric fleets not only visible, but very compelling.

Critical success factors include:

- Development of a 500kW wireless charging system.
- Development of a Class-8 truck powertrain with a battery pack capable of reliably and repeatedly charge at a greater than 3C rate up to 500 kW.
- Development of a modular direct MV 3-phase AC to DC power converter.
- Achieve MV grid system to vehicle battery efficiency of 92%.