

Development and Demonstration of Advanced Engine and Vehicle Technologies for Class 8 Heavy-Duty Vehicle (SuperTruck II)

Maarten Meijer Ph.D. – Principal Investigator

PACCAR Inc.

June 15, 2023

Project ID: ACE124

Overview

Timeline

- **Start Date:** October 2017
- **End Date:** December 2023
- **Percent Complete:** 85%

Budget

Total Project Funding

DOE: \$20M

Partnership: \$20M

FY 2022 Funding: \$40M

Barriers

Identifying Cost Effective, Production Representative Process For Cab Structure

Cost, Robustness And Packaging Needs Of Engine Technologies To Achieve 55% BTE

Ability To Demonstrate Benefits In More Than One Application/Use Case

Partners



Objectives and Relevance

- **Overall Objectives**

- > 120% Freight Efficiency Improvement Relative To a 2009 Baseline
- ≥ 55% Engine Brake Thermal Efficiency
- 3 Year Payback Period on Developed Technologies

- **Objectives This Period**

- 55% BTE Engine and WHR Demonstration
- Complete Powertrain Proof-of-Concept
- Vehicle Demonstrator Build
- ROI Calculations

- **Impact**

- Evaluation of Higher Risk Technologies With Potential For Energy Efficiency
- Potential Modernization of Key Technologies in Freight Transport Industry
- Evaluation of Impact of Technologies in More Than One Real-World Drive Cycle

Program Outline

Budget Period 1

Analysis & Baseline Testing

- Simulation To Evaluate Engine, Powertrain And Vehicle Efficiency Building Blocks
- Baseline Testing



Budget Period 2

Design & Prototype Build

- Engine Design
- Powertrain And Controls Architecture Selection
- Prototype Builds
- Cab And Chassis Development



Budget Period 3

Component Test And Validation

- Vehicle Controls Development
- Proto Vehicles Testing
- New Engine Technologies Testing
- Hybrid Powertrain Testing
- WHR Integration And Initial Testing



Budget Period 4

Powertrain Testing & Engine Build

- Powertrain And Vehicle Integration
- Engine Efficiency Demo
- Initial Testing Of Drivability & Fuel Economy
- Engine & WHR 55% BTE Demo



Budget Period 5

SuperTruck Build & Freight Efficiency Demo

- SuperTruck Vehicle Build
- SuperTruck Freight Efficiency Demo >120%
- ROI on New Technologies

Remaining Milestones


Milestone	Type	Description
SuperTruck II Vehicle Build is Complete	Technical	SuperTruck II Vehicle is Built
SuperTruck II Vehicle Field Test Complete	Technical	Powertrain for SuperTruck II Demonstrates viability of greater than 100% Improvement in Freight Efficiency in Powertrain Test Cell
Simple Payback Demonstrated	Technical	SuperTruck II Vehicle is Field Tested

Key Technologies

Engine

Next Gen. PACCAR MX

- Long Stroke Concept
- Engine Efficiency Over WHR
- 48V Aux. / FEAD Removal
- Ultra Low NOx Compliant



Powertrain

48V Mild-Hybrid


- 30kW P2.5 e-Motor / Generator
- Supports Vehicle Aux. Electrification
- Dev. of 48V Components
- Next Gen. Li-Ion Batteries



Chassis

Light-Weight & Modular


- Supports All New Powertrains
- 30% Weight Savings Chassis and Suspension
- Ease of Manufacturing
- e-Steering




Tractor


Aerodynamic Cabin

- Energy Efficient
- e-HVAC
- Predictive e-Hoteling
- System Level Energy Management




Engine Concept





Gasoline Compression Ignition


- High BTE and ULN
- Experiments Completed
- Diesel is Prime Path



Close-Coupled EAS

- 48V e-Heater
- Carb ULN 2027 (FTP 0.02 g/bhp-hr)
- Included in Vehicle Demonstrator


Waste Heat Recovery




- Cummins WHR System, Tailored to PACCAR Engine
- Multiple Waste Heat Streams
 - Exhaust
 - Coolant
 - Charge Air Coolers

55% BTE Demonstrator Results

Design Targets:



Testbed Measurements:



Powertrain

Powertrain Efficiency 40% Improvement

Base Powertrain


21%

Mild Hybrid / Electrification


13%

Low Rolling Resistance Tires

6%



48V Battery-Pack




e-Motor

2 Speed Gearbox

Vehicle Freight Efficiency

Powertrain Efficiency 40% Improvement



Engine / Transmission / Axles

Mild Hybrid / Electrification

Low Rolling Resistance Tires

Weight Reduction 28% Reduction




Systems Engineering

Modular Integration

Materials Application

Aerodynamics 63% Reduction




Ideal Shape

Enclosed Wheels

Trailer Skirt & Pontoon


Cab Structure (BIW), Front End



BIW Design is complete and in process of being built by TPI Composites.



Roof Sub-Assembly



FEA Complete And Passed Stress And Modal Requirements



Sliding Fender Components Near Completion



Floor Sub-Assembly



Front Wall





Headlights Are Completed And Pending Shipment


Interior Cabin and HVAC



Driver seat structure and belt system integration completed. Seat styling & Trim covers development on schedule




Interior panels fabrications in process. Tooled corner ceiling panels shown



Sofa and Bunk design & FEA completed.



Interior Cabin Rendering



HVAC unit completed, tested, and on hand






Trailer Development



Trailer design completed and is being assembled at Stoughton




Trailer Suspension complete




Trailer Skirt Design complete, and parts are currently being fabricated at Ridge


Chassis & Powertrain





Two Circuit Cooling
Two-Stage iCAC
40% Frontal Open Area
Integrated Air Cleaner
Centrifugal 48V Pusher Fans




IY2027 Ultra-Low NOx
Close-Coupled SCR




Two-Stage
iCAC
Integrated
coolant
distribution



Narrow Track Axle - Aerodynamics
Reduced Scrub – Steering Power
Rack & Pinion – Weight / Ackerman




Combined Fuel / Air / Drier/ DEF Module




Lightweight Triangulated 3-Link
Suspension


3D Routing




LT & HT Coolant System




Electrical and Power Electronics



Vehicle Routing Strategy Complete




Air Brake System



DEF & Fuel System

Electrical & Controls

12V/ 48V Electrical



- High Current Power Distribution Complete
- Electrical Component Definition Complete
- Harness Requested to Suppliers

Controls & Architecture



GCM 196




RCM 112











MicroAutoBoxII

- CAN Architecture for Demonstrator - Finalized
- Controls Development - Complete
- Unit Testing of the Individual Subsystem - Complete
- Bench Testing of Component - Complete
- Fault Management Implementation - In Progress

Freight Efficiency Contributions



Partnerships/Collaborations

	Vehicle Development, Vehicle Level Supervisory Controls
	Engine and Powertrain Development, Program Administration
	Electrified Powertrain, Transmission, and Air Management Systems Development
	Engine Development
	Drive Cycle Development, and Thermal Management
	Waste Heat Recovery Integration
	Axle Integration
	Tire Development
	Model Development for Cabin Hoteling Optimization

Remaining Challenges

- **Complete Vehicle Build**
- **Vehicle Demonstration:**

National Average Drive-Cycle Selected Using Specialized NREL Algorithm

Key metrics


Road Grade

Hill length


Altitude

Max. Speed

Hotel Loads



I-94 Beach, ND to New Salem, ND



Summary

- **Program Completion on Time, Within Budget While Meeting Targets**
- **Engine**
 - 55.7% BTE Demonstrated
 - Tech Transfer for Commercialization
- **Powertrain**
 - Mild Hybrid Powertrain & 48V Battery System Validated & Integrated in Final Vehicle Demonstrator
- **Vehicle**
 - Updated Freight Efficiency Roadmap To 150% Improvement
 - Final Vehicle Demonstrator Build Ongoing
 - Freight Efficiency Demonstration Preparations Ongoing

TECHNICAL BACKUP SLIDES