2023 DOE Vehicle Technologies Office Annual Merit Review

Project Sila: An Arctic CNG Pilot Test Program

Principal Investigator: Keith Patterson

Presenter: Troy Tempel

Company: ASRC Consulting & Environmental Services, LLC

(ACES)

Date: 4/14/2023

Project ID: TI152



Project Overview



Timeline

• Start: March 2022

• End: July 2025

• Percent Complete: 30%

Budget

Total Project Funding

• DOE Share: \$1,064,076

• Cost Share: \$1,064,076

• Total Expended

• DOE Share: \$221,880

• Cost Share: \$221,880

Barriers

- CNG operations in low temp Arctic environment
- High CO₂ content in fuel
- Operator and maintenance acceptance

Partners

- Onboard Dynamics
 - GoFLO Natural Gas Compressor
 - GoFILL CNG Refueler
- PAPE' Kenworth
 - Kenworth T880 Trucks (ISX12-G)
 - Agility Fuel Systems CNG Upfit



Objectives

- Pilot test CNG upfitted HD trucks
- Install Arctic rated CNG fueling station
- Reduce carbon emissions
- Benchmark CNG vs. diesel performance

VTO Technology Integration Goals

- Improves fuel diversity with an underutilized source
- Increased local resiliency with a readily available fuel source
- Potential to reduce greenhouse gas emissions through alternative fuel use

Impact

- Pilot project will document the feasibility of CNG operations in the Arctic Resiliency
- Addresses concerns with a high CO2 fuel source
- Provides training to both operator and maintenance personnel on CNG operation, with the potential to deploy this technology to other parts of the North Slope

Project Approach



Budget Period 1

Procurement & Install:

- Vendor and equipment selections
- Arctic and CNG upfitting
- Factory acceptance testing
- Shipping
- Compression equipment install and tie-in
- Truck delivery

Budget Period 2

First Year Operation:

- Equipment troubleshooting
- Maintenance and shop training
- Operator training
- Data collection

Budget Period 3

Second Year Operation:

- Continue vehicle and equipment operation
- Continue data collection
- Prepare data analytics report regarding CNG vs. Diesel operation
- Assess the project objectives and make recommendations regarding continued operation

Milestones: Budget Period 1



- **✓** Equipment Procurement
- Off-the-shelf designs
- Order submitted March 2023
- ✓ Compressor Design
- Actively worked with Onboard Dynamics
- Arctic and CO2 barriers
- **✓** Compressor Location
- Site plan drafted, need to finalize with tie-in locations
- Onboard Dynamics allowed for flexible install
- **✓** Truck Procurement Cost
- Trucks were within budget
- <u>Go</u>
- **✓** Truck Procurement
- Order submitted with PAPE' Kenworth March 2023
- Go

Truck Delivery to AK

- Truck delivery not anticipated to be an issue
- <u>Go</u>

Compressor Installation

- Compressors will be tested and staff training will occur at Onboard Dynamic's facility
- Minimal install scope (no electrical or permanent foundation necessary)





Commission Equipment

- Test compressors & fill station
- Test trucks and benchmark

Operator Training

- Compressor training
- Train drivers on filling procedures

Equipment Operations

- Begin full time operations
- Includes compressor, refueling station, and trucks

Equipment Reliability

- Monitor performance
- Refine best practices for monitoring (fuel consumption, emissions)



Data Collection & Analytics

- Continue operations and collecting data
- Begin analyzing data

Preliminary Reporting

- Deliver report of first year of operations
- Compare truck performance against project objectives

Maintenance Monitoring

Conduct maintenance cost analysis

Final Reporting

- Deliver reporting on 24 months of CNG operation
- Compare against diesel fueled fleet

Operation Cost & Emission

- Determine if program is sustainable
- Go / No Go

Project Accomplishments: High CO₂ Content



Prudhoe Bay natural gas contains high CO₂ content

- 12% CO₂ as produced from the reservoir
- Minimal treatment infrastructure exists
- High compression pressure can cause carbonic acid to form

CNG Compression Vendors

- High CO₂ content was a concern for several CNG vendors
- Most required additional gas scrubbing

Onboard Dynamics

- GoFLO Compressor operates at slightly lesser pressure
- Will utilize corrosion resistant materials
- Operates much differently than traditional gas compressors
- No major electrical demand



Project Accomplishments: Arctic Packaging & Install



Prudhoe Bay design temps down to -40F


- Majority of CNG compression units would require additional heating to maintain -20F operating temp
- GoFLO compressor design can utilize a traditional block heater and battery blankets, commonly used in Prudhoe Bay


Weather Resistant Enclosure

GoFLO unit is naturally weather resistant by design,
additional insulation and heat trace may be included

Permafrost Install

- GoFLO unit is installed with compact legs
- Minimal heat transfer to the pad and permafrost
- Traditional compressor would require a thermosiphon concrete pad or insulated pilings





Collaboration & Coordination Among Project Team



Lead Organization:

ASRC Consulting & Environmental Services, LLC

Partner Organizations:

- Onboard Dynamics: CNG compression equipment
- PAPE' Kenworth: CNG trucks
- Agility Fuel Systems: CNG upfitting
- Norgasco Inc: Natural gas utility

Community Partners

Arctic Slope Regional Corporation







Contribution to Energy Equity & Environmental Justice



The North Slope of Alaska:

- Arctic Slope Regional Corporation consists of 7 communities, three of which have natural gas sources
 - Barrow, Wainwright, Atqasuk, Nuiqsut, Kaktovik, Pt. Lay, and Pt. Hope
- Utilizing a local fuel source will drastically reduce vehicle fueling costs and emission output
 - Diesel is currently barged up seasonally
- Air quality will be further increased as commercial fleets transition to CNG source









Goals

- Pilot test CNG upfitted heavy duty trucks
- Install & operate an Arctic rated CNG fueling station
- Share the emissions & performance info with local communities

Current Progress

- Compression equipment selected and on order
- Trucks on order
- Preliminary install and layout plan

Upcoming

- Compression equipment install
- Truck delivery
- Commissioning and training
- Operation